

**Office of the Director, Odisha State Maritime Museum
Jobra, Cuttack.**

QUOTATION CALL NOTICE NO.- 13 OF 2017-18

Quotation for the work:- Construction of Washroom attached to Multimedia hall of Odisha State Maritime Museum, Jobra, Cuttack."

vide D.R. No. 22(M) of 2017-18 of the Executive Engineer, Mahanadi South Division, Jobra, Cuttack.

Sealed quotations in plain paper are hereby invited from eligible Contractor having valid license/ registration certificate, PAN card, GST number for Execution of work as scheduled below. The quotation should reach to the undersigned on or before Date. 02.01.2018 upto 3:00pm & the same will be opened at 4:00 PM in presence of quotationer or their authorized agent.

The undersigned reserves the right to reject any or all quotations without assigning any reason thereof.

Sl. No.	Item	Unit	Qty.	Rate in Figure
1)	Dismantling brick masonry in lime or cement mortar above 3M height including stacking the useful materials for reuse and removing the debris within 50M lead etc complete.	Cum	1	
2)	Earth work in excavation in in foundation in all kind of with 0 extra lead and 0 extra lift over initial lead of 50m and initial lift of 1.5m including dressing and levelling the bed and sides and depositing the excavated earth away from away site etc complete per direction of the Engg-In- Charge.	100 cum	1	
3)	Cement concrete (1:3:6) with 25mm size hard granite metal including cost, carriage, royalty and taxes of all material etc complete as per direction of the Engineer-in charge.	Cum	1	
4)	Brick work with K.B. bricks 25cm x 12cm x 8cm size having crushing strengthnot less than 75kg/cm ² with dimension tolerance +8 percent in cement mortar (1:4) in foundation and plinth including cost, conveyance & Royalty of all materials etc. complete as per direction of Engg-In-Charge.	Cum	1	
5)	Rigid and smooth centring and shuttering for R.C.C. works including false work and dismantling the same after the required perid of casting including cost of all materials complete in ground floor.	Sqmt.	1	
6)	Reinforcement for R.C.C. work including cutting, bending and tying the grill and placing in position including the cost of binding wire 18 to 20 gauge and reinforcement steel etc complete as directed by the Engineer-in-charge.	Qntl.	1	
7)	Cement concrete (1 : 1.5 : 3) with 12mm size hard granite chips for R.C.C. work including cost, carriage, royalty and taxes of all material etc complete as per direction of the Engineer-in charge.	Cum	1	
8)	12mm thick cement plaster(1 : 3) for brick work including cost of all materials, carriage royalty etc complete.	Sqmt.	1	

9)	Finishing surface of walls with cement based wall putty (Water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials, taxes, labour T&P etc complete.	Sqmt.	1	
10)	Supplying, fitting and fixing of Aluminium door with anodised Al. door Section of 9202 as vertical member, 9201 as top and 9200 as middle and bottom member with framw section No.9221 and tapered clip No. 4660 and the frame to be completed by means of jointing angle No.1855 including all fitting, cost of all materials, all taxes, labour and T&P etc complete as per direction of the Engineer-in-charge.	Sqmt.	1	
11)	Supplying, fitting and fixing vitrified tiles in floors of size 600mm x 600mm of approved make conforming to IS : 13755 with application of polymer modified quick set cement based water resistant adhesive conforming to IS : 15477 of 3mm thick bed and filling joints with white cement of approved quality including cost of all materials, labour T&P etc required for the work all complete as per direction of Engineer-in charge. (For repair work only)	Sqmt.	1	
12)	Fixing (Glazed)tiles in dados skirting and risers of steps on 12 mm thick bed of cement plaster 1 : 3(1 cement : 3 sand) jointed with neat cement slurry mixed with pigment to match the shade of tiles including rubbing and polishing etc complete.	Sqmt.	1	

(Twelve) items only.

Yours Sincerely,

Director
Odisha State Maritime Museum
Jobra, Cuttack.

Memo No..... / Date.....

Copy submitted to the Superintending Engineer, Eastern Circle-I, Cuttack -Cum- Member Treasurer, OSMM, Jobra ,Cuttack for favour of information & necessary action.

Director

Memo No..... / Date.....

Copy submitted to the Executive Engineer, Mahanadi South Division-I, Cuttack - cum- Member Secretary , OSMM, Cuttack for favour of information & necessary action.

Director

Memo No. 267 (2) / Date 28-12-2017

Copy to Notice Board./ Website for wide publication.

Director
R/h
28-12-17