

OFFICE OF THE DIRECTOR ODISHA STATE MARITIME MUSEUM, JOBRA,
CUTTACK.

QUOTATION CALL NOTICE NO.1 OF 2015-16

Quotation for the work: - Rewinding &
Repair of 5 HP submersible pump with new
fixing of control panel board at OSMM,
Jobra, Cuttack.

Vide D.R No. 30(M) of the Executive
Engineer, Mahanadi South Division,
Cuttack.

Sealed quotations are invited for intending eligible electrical repairing firms having registration certificate, PAN Card and VAT clearance for the work as seclude below. The quotation should reach before the under sign on or before 10.08.2015 up to 3:00 PM and the same will be opened on the very day at 4:00 PM in presence of quotations or their authorized agent.

The undersign reserves the right to reject the quotations without assigning any reason thereof.

Sl. No	Description of item	Qnty.	Unit.	Rate in figure
1.	Supplying all materials,labour T & P and rewinding of 5 HP submersible motor with supply of appropriate size of water proof PVC insulated copper wire including tapping and jointing properly with supply of jointing materials etc. all complete.	1	Each	
2.	Supplying all materials, labour, T & P and making G.M. Bush as per sample and fitting to the motor etc. all complete	4	Each	
3.	Supplying all materials, labour, T & P and making stainless steel bush as per sample and fitting to the motor complete	4	Each	
4.	Supplying all materials, labour, T & P and making thrust bearing and thrust plate complete set and fitting to the motor.	1	Set	
5.	Supplying all materials, labour, T & P and jointing the insulating flat cable with motor terminal with necessary jointing materials like M.Seal steel grip tape etc. complete.	2	Each	
<u>REPAIR OF PUMP</u>				
6.	Supplying all welding materials, labour, T & P and welding the stainless steel pump shaft with key way cutting, finishing etc. all complete.	1	Each	

7.	Supplying all materials, labour, T & P and making stainless steel bush as per sample and fitting to the pump	5	Each	
8.	Supplying all materials, labour, T & P and making brass impeller ring and fixing to the pump.	5	Each	
9.	Supplying all welding materials, labour, T & P and welding the impellor and turning the same etc. all complete.	4	Each	
10.	Supplying and labour, T & P and opening of the pump and overhauling, cleaning and assembling of pump of all spare parts fitting and testing charges.	1	Each	
11.	Supplying 6 sqmm 3 core PVC submersible copper flat cable to the motor.	3	Mtr.	
12.	Supplying all materials, labour, T & P for lifting and lowering of 5H.P pump set from tube well with column pipe etc. complete as per direction of Engineer –in-charge.	1	Item	
13.	Supplying and fixing of 5H.P submersible motor's new control panel board with supply of M.S clamp, nut and bolt etc. all complete.	1	Mtr.	
14.	Panel board connection with 3x 7/18 copper wire from main switch to control panel board.	9		
15.	Deduction cost towards burnt copper wire.	(-)		

(Fourteen item only)

Yours Sincerely,

Director
Odisha State Maritime Museum
Jobra, Cuttack.

Memo No. _____ / Date. _____

Copy submitted to the Superintending Engineer, Eastern Circle, Cuttack for favour of information & necessary action.

Director

Memo No. _____ / Date. _____

Copy submitted to the Executive Engineer, Mahanadi South Division, Cuttack for favour of information & necessary action.

Director

Memo No. _____ / Date. _____

Copy to Notice Board/ website for wide publication.

Director